Sectt. II-27—36,006—30-10-37.

P.W.D

(1938) Department.

M.C. SERIES.

G.O. No. 1330

DATED 27/01/38

[Despatch Abstract]

Buildings - South Kanara - Puthur veterinary dispesnary - Improvements - Revised estimate - Rs.2860/- approved.

C.F. 30.

Civil Veterinary **DEPARTMENT.**

Received ..... 19 *Registered* Dev. 2555. III 19
26.5.38

Subject.

Buildings- Veterinary Dispensary, Puthur (South Kanara District)- Improvements- Plans and estimates- Submitted to Government.

ENCLOSURES.
No. Plans and estimate
Spare copies.....

R.O.C. No. 1793-C/36.

Station Royapettah P.O., *Dated the* 20th May, 19 38.

From (Name) P.T.Saunders Esq, O.B.E, M.R.C.V.S, I.V.S,
(Designation) Director of Veterinary Services, Madras.

To The Secretary to the Government of Madras,
DEVELOPMENT Department.

Sir,

Government in their Order No.899, Public Works Department, dated 29th April 1937 approved an expenditure of Rs.1,800/- on certain improvements to the Veterinary Dispensary buildings at Puthur in South Kanara District, viz. construction of an in-patient cattle shed, provision of a roof over the operating shed, provision of glazed verandahs etc. The District Veterinary Officer, Calicut has now forwarded plans and detailed estimates amounting to Rs.2,860/- for the work cited above for obtaining revised administrative approval of Government as the amount of the detailed estimate is far in excess of that of the approximate estimate approved in the

G.O.

G.C. quoted above. The plans and the estimates received from the District Veterinary Officer are herewith submitted and I request Government to be pleased to accord their revised administrative approval to the same.

2. The excess in the amount of the detailed estimate over that of the approximate estimate is accounted for by the following facts:--

(a) In the approximate estimate, an area of 600 sq.feet alone was provided for the operation shed but it has been altered in the detailed estimate to 810 sq.feet;

(b) Provision has been made in the detailed estimate for ceiling tiles for the portico and the existing verandah of the Veterinary Dispensary to make them sun-proof;

(c) In addition, provision has also been made for the construction of a culvert in front of the main gate. The drain in front of the gate has a deep gradient and during rainy season, the drain becomes too deep to cross with safety. The construction of a culvert in front of the main gate of the Veterinary Dispensary is thus considered essential.

(d) Lastly provision has been made for R.C. shelves to the store rooms. The accommodation available at the Veterinary Dispensary is insufficient and additional accommodation has to be found by provision of racks or shelves in the walls for keeping articles of stores, records, etc.

I have the honour to be,
Sir,
Your most obedient servant,

for ~~Director of Veterinary~~
Services, Madras.

T.s.s/23.5.38.

GOVT. SECRETARIAT TO GOVT.
3-JUN 1938
2436
PUBLIC

To A.S.

Govt. Dept

May be forwarded to P.W.D. with support.

Dew No. 2555-M/38
2-6-38

31.5.38

Report to accompany the estimate for the Improvements to the Veterinary Dispensary at Puthur.

Amount of estimate Rs. 2860/-

Item 11 on page 200 of the Register of buildings
Capital cost Rs.3324/-

This estimate is prepared on the requisition of the District Veterinary Officer and also as approved by the Government in G.O.No. 899 Agks dated 29-4-37.

The existing dispensary consists of two small store rooms, two dispensing rooms and a long verandah. Difficulty is experienced in storing all the stock medicines and also in dispensing. For the former it is proposed to provide R.C. shelves for the two small store rooms and for the latter to provide a portico in the front and provide glazed and iron barred windows for the verandah and portico in order to use/ the same as a dispensing and consulting room.

There is no place to keep the animals coming for --- treatment or a place for conducting operations. A shed with 3 partitions for keeping 6 animals and an open shed for operation operating on the animals is also therefore provided The entrance into the hospital has no approach road and there fore it is proposed to provide a small culvert with 12" Hume pipes and to form an approach road.

A.G.G. Barclay 2.4.38

Executive Engineer.

Res: Coast Division.

29.3.38